



Pavement Rehabilitation Works — Woodstock Street and John Street Intersection

PROJECT:

This project provides for pavement rehabilitation works on Woodstock Street at its intersection with John Street, Maryborough.

PROJECT ESTIMATE:

\$102,000

PROJECT SCOPE OF WORKS

The Project scope is as follows:

- Cold milling of existing asphalt surface;
- Bitumen/asphalt surfacing;
- Adjustments to manhole/service lids;
- Replacement of pavement marking.

The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.





INDICATIVE PROJECT MILESTONES	
April 2020	Final Design
June 2020	Tender Period
June /July 2020	Construction Period
August 2020	Project Completion

Note: Project milestones are subject to contract and weather and may change.

Pavement Rehabilitation Works —

Woodstock Street and John Street Intersection



NOTES

1. ALL EXISTING PAVEMENT MARKING SHALL BE REINSTITATED. THE LOCATION OF UNDERGROUND SERVICES ARE BASED ON DIAL BEFORE YOU DIG INFORMATION ONLY.
- 2.

WOODSTOCK STREET CONTROL LINE SETOUT		
PT	CHANGING	EASTING
P 1	0.000	470886.128
P 2	38.103	470715.531
P 3	73.244	470742.611



DATUM RL: 11.00		LONGITUDINAL SECTION - WOODSTOCK STREET															
VERTICAL ALIGNMENT	LEVEL DIFFERENCE CUT - / FILL +	12.31	12.32	12.32	12.33	12.33	12.33	12.33	12.36	12.41	12.45	12.46	12.47	12.48	12.52		
		0.00	0.02	0.02	0.03	0.03	0.03	0.03	0.09	0.10	0.09	0.01	0.01	0.03	0.03		
DESIGN SURFACE LEVEL		12.322	12.333	12.343	12.347	12.347	12.347	12.347	12.366	12.411	12.454	12.462	12.47	12.48	12.52		
EXISTING SURFACE LEVEL		12.32	12.32	12.33	12.33	12.33	12.33	12.33	12.36	12.41	12.45	12.46	12.47	12.48	12.52		
CHAINAGE		0.000	5.000	10.000	15.000	20.000	25.000	30.000	35.000	40.000	45.000	50.000	55.000	60.000	65.000	70.000	73.244

HORIZONTAL SCALE 1:500
VERTICAL SCALE 1:50