

## Removal of Loose Rock—Urangan Seawall

### PROJECT:

This project provides for the removal of loose rock from a 315m section of the Urangan Seawall from approximately 551 Esplanade to 564 Esplanade Urangan. The small loose rock will be separated from the larger rock and sand and removed for future reuse. The sand will then be reinstated at the toe of the concrete staircase.

These works are being undertaken to address the risk of the small rock becoming a projectile during severe weather events posing a risk to users of the area.

PROJECT ESTIMATE: \$40,000

### PROJECT SCOPE OF WORKS:

- Screening and removal of small rock;
- Importation of sand from Booral Pit should this be considered a requirement following removal of the small rock from this area.

The traffic management plan that will be put in place for the duration of the works will be developed prior to works commencing. Due to the seawall's location, access to the site will be gained through Council's beach access point south of the project along the Esplanade. (see plan attached)



### INDICATIVE PROJECT MILESTONES

August 2021	Construction Period
August 2021	Project Completion

Note: Project milestones are subject to contract and weather and may change.

Removal of Loose Rock—Urangan Seawall

