

Sectional Kerb and Channel and Footpath Replacement—Keith Street

PROJECT:

This project provides for the replacement of a 77m section of the kerb and channel on the western side of Keith Street between 14 Keith Street and 380 Alice Street.

The works are being undertaken as a result of inspections carried out as part of Council’s ongoing asset inspection program which identified that the kerb and channel was showing signs of failure and distress.

PROJECT ESTIMATE:

\$120,000

PROJECT SCOPE OF WORKS:

The Project scope is as follows:

- Excavation and earthworks;
- Replacement of existing kerb on the western side of Keith Street between 14 Keith Street and 380 Alice Street;
- Reconstruction of 4 existing vehicle crossovers at 14, 16 and 18 Keith Street and 380 Alice Street; (*reinstatement works will be completed in plain concrete only*). Existing gravel driveways will be reinstated in their current form (gravel);
- Replacement of sections of pathway in front of 16 and 18 Keith Street;
- Subsoil drainage works;
- Reconnection of stormwater to outlets;
- Tree trimming if required and topdressing and turfing of disturbed areas.



The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

INDICATIVE PROJECT MILESTONES

INDICATIVE PROJECT MILESTONES	
Oct 2022	Final Design
Feb/March 23	Construction Period
April 23	Project Completion

Note: Project milestones are subject to weather and may change.

