

## Footpath Construction – Doolong South Road (College Way to Parklands)

### PROJECT:

This project provides for the construction of a 2.5m wide concrete shared pathway on the eastern side of Doolong South Road from College Way to 650m south.

This pathway project was identified for completion as part of Council’s Active Travel Strategy and will complete a missing link in this location.

### PROJECT ESTIMATE:

\$750,000 (this project is funded through the State Government’s Works for Queensland Funding Program)

### PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Excavation and earthworks;
- Removal of vegetation;
- Importation of fill;
- Culvert extension and concrete works;
- Subsoil drainage;
- New pavement construction;
- Sectional kerb and channel construction;
- Barrier rail;
- 2 x new kerb ramps at College Way;
- Construction of a 2.5m wide concrete pathway on the eastern side of Doolong South Road from College Way to 650m south;
- Topdressing and turfing of disturbed areas.



The traffic and pedestrian management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

### INDICATIVE PROJECT MILESTONES

INDICATIVE PROJECT MILESTONES	
September 2023	Final Design
October/January 2024	Construction Period
February 2024	Project Completion

Note: Project milestones are subject to weather and may change.



### Footpath Construction – Doolong South Road (College Way to Parklands)

