

Footpath Construction – Woodstock Street (Neptune Street to Frank Street)

PROJECT:

This project provides for the construction of a 1.3m -1.9m wide concrete footpath for a distance of approximately 180m on the northern side of Woodstock Street between Neptune Street and Frank Street to provide access to the on-street parking area located adjacent to the Maryborough Hockey fields.

This project was identified for completion as part of a missing link from the existing footpath on the northern side of Woodstock Street.

PROJECT ESTIMATE:

\$95,000 (this project is funded through the State Government’s Transport Infrastructure Development Scheme)

PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Excavation and earthworks;
- Construction of a new 1.3m-1.9m wide concrete footpath in Woodstock Street from Neptune Street to Frank Street;
- Footpath links to existing Maryborough Hockey Fields gates;
- Kerb ramp at the Neptune Street and Woodstock Street intersection;
- Reinstatement of signage;
- Topdressing and turfing of disturbed areas.



The traffic and pedestrian management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

INDICATIVE PROJECT MILESTONES	
October 2023	Final Design
Nov/Dec 2023	Construction Period
December 2023	Project Completion

Note: Project milestones are subject to weather and may change.

Footpath Construction – Woodstock Street



