

Kerb and Channel Replacement – Elliott Street (Banana Street to Maryborough Street)

PROJECT:

This project provides for the replacement of the kerb and channel on the eastern side of Elliott Street between Banana Street and Maryborough Street.

The works are being undertaken as a result of inspections carried out as part of Council’s ongoing asset inspection program which identified that the kerb and channel was showing signs of failure and distress.

PROJECT ESTIMATE:

\$177,000

PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Excavation and earthworks;
- Replacement of existing kerb on the eastern side of Elliott Street between Banana Street and Maryborough Street;
- Reconstruction of 5 existing vehicle crossovers at 108 Banana Street, 5, 7 and 9 Banana Street and 5 Maryborough Street. *(Note: reinstatement works to be completed in plain concrete only);*
- Subsoil drainage works;
- Reconnection of stormwater to outlets;
- Road pavement reinstatements work against excavated kerb areas;
- Topdressing and turfing of disturbed areas.












The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

| INDICATIVE PROJECT MILESTONES | |
|-------------------------------|---------------------|
| September 2023 | Final Design |
| Nov/Dec 2023 | Construction Period |
| December 2023 | Project Completion |

Note: Project milestones are subject to weather and may change.

Kerb and Channel Replacement – Elliott Street

LEGEND

| | | | |
|-----------------------------------------------------------------------------------|-----------------------------|-----------------------------------------------------------------------------------|-----------------------------|
|  | EXISTING LOT BOUNDARY |  | PROPOSED KERB AND CHANNEL |
|  | EXISTING CONCRETE EDGE LINE |  | PROPOSED PAVEMENT SURFACING |
|  | EXISTING CONCRETE |  | PROPOSED CONCRETE |
|  | EXISTING GRAVEL |  | TURFING |
|  | PROPOSED CUTBACK LINE | | |

