

Footpath Construction – Rocky Street (60 Rocky Street to Walker Street)

PROJECT:

This project provides for the construction of a 1.5m wide concrete footpath on the western side of Rocky Street from 60 Rocky Street to Walker Street.

This project was identified for completion as part of a missing link in this area.

PROJECT ESTIMATE:

\$60,000

PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Excavation and earthworks;
- Construction of a 1.5m wide concrete footpath on the western side of Rocky Street from 60 Rocky Street to Walker Street;
- New concrete driveway at 140 Walker Street;
- Removal of three (3) trees and trimming of tree located at 140 Walker Street;
- Topdressing and turfing of disturbed areas.



The traffic and pedestrian management plan that will be put in place for the duration of the construction period will allow for a lateral shift of traffic with a two-way traffic arrangement being maintained in Rocky whilst the works are completed.

INDICATIVE PROJECT MILESTONES	
June 2024	Final Design
March 2025	Construction Period
April 2025	Project Completion

Note: Project milestones are subject to weather and may change.

Footpath Construction – Rocky Street

